

PI

31-9-17W

INFORMATION REQUEST FORM

FROM: Petroleum Information Corp.
1007 Century Plaza
Wichita, Ks 67202

RE: Well Completion Report. Please complete this form and return it in the enclosed envelope. We and the Industry thank you for your cooperation.

Operator LAWBAND DRILLING API# 15-163-21293 County ROOKS
Well # 4 Lease Name GANDUNG Sec 31 Twp 9 Rge 17W
Contractor LAWBAND DRILLING Geologist ERIC WADDELL Loc NW SW SE
Start Date 4-29-81 Completed Date 5-4-81 Ftg _____
Casing Record: Size _____ Depth _____ Sx Cmt _____

Surface Production 4 1/2 _____ 3639 _____ 2 Staged at Anhydrite
Total Depth 3640 PBD _____ Type Electric Logs GAMMA RAY - CORR.
RADIATION GUARD LOG Elev: KB 2111 GR 2106
Formation tops: Spl _____ Log _____

Cores:	Interval	Recovery	Description	
				Jopoka 3019 -908
				Heebner Sh. 3233 -1122
				Laronto LMS 3261 -1150
				Lansing Kc 3280 -1169
				Base of Kc 3508 -1397
				Conglomerate 3521 -1410
				Simpson Dol 3565 -1454
				Arbuckle Dol 3588 -1477

STS: Form. - Interval - Times - Pressures - Temp - Recovery

PERFORATION - TREATMENT RECORD

Perfs	Interval	Formation	Acid	Sand,	Fluid	Test
9	3549-52		250 gal 15% HCL ACID			
12	3539-43		5 gal 1-2 INHIBITOR			
12	3525-29		250 lbs BANZOIC ACID			
5	3458-60					
9	3440-44		Top 3 intervals - 500 gal 15% HCL ACID			
7	3317-20		1 gal 1-2 INHIBITOR			
			INITIAL PRODUCTION			
			500 gal 15% HCL ACID			
Pump/Flow	Oil - Gas - Wtr /Day	Formation	Interval	Date		
Pump	18 BBL 40			6-25-81		