

JAN 24 1970

32-9-17W

32-9-17W

NE SE SE


15-163-20266

DRILLERS LOG

COMPANY:
CONTRACTOR:
LEASE NAME:
LOCATION:

ELEVATION:
SURFACE CASING:
COMMENCED:
COMPLETED:
OIL STRING:
ROTARY TOTAL DEPTH:

Armstrong & Jackman
Aspen Drilling Co.
Hilgers #1
NE-SE-SE Sec. 32-T9S-R17W
Rooks County, Kansas
2116' K. B.
5 jts. (201') 8 5/8"
November 11, 1969
November 20, 1969.
114 jts. (3588') 5 1/2"
3589'



<u>FORMATION</u>	<u>DEPTH</u>
Shale & Sand	780
Sand & Shale	915
Shale	950
Sand	1100
Shale & Shells	1374
Anhydrite	1411
Shale & Shells	1880
Shale & Lime	2315
Lime & Shale	3060
Lime	3494
Lime & Shale	3565
Lime	3589

Ran 5 jts. (201') 8 5/8" casing set at
208' w/150 sacks Sunset. Cement
circulated.

DST #1, 3238-3270

Ran electric log.

Ran 114 jts. (3588') 5 1/2" casing set at
3586' w/150 sacks, w/20 bbls. pre-flush.

LOG TOPS

Heebner	3229
Toronto	3246
Kansas City	3269
Arbuckle	3570

AFFIDAVIT

State of Kansas)
) ss:
County of Barton)

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

William S. Schachle
Willaim S. Schachle AFFIANT

Subscribed and sworn to before me this 25th day of November, 1969.

