

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - PHILLIPS PETROLEUM COMPANY
Farm - Nettie No. 1

15-163-71196
SEC. 34 T. 9 R. 17W
SE SE SW

80' SL, 2310' WL of SW/4

County. Rooks
KANSAS



Total Depth. 988
Corrn. 1-14-49 Comp. 4-6-49
Shot or Treated.
Contractor.
Issued. 5-14-49

CASING:

8" 602'
6" 830'

Elevation. 2040 act.

Production. S. W. D. W.

Figures Indicate Bottom of Formations.

surface soil	10
post rock	70
shale gry and blue	75
shale blue	140
shale	265
shale blue	325
shale	390
lime	400
shale gry	490
sand	500
shale gry	535
shale blue	590
red rock	600
shale	615
red roc	625
sand	640
red rock	645
sand	700
shale blue	720
sand	730
shale blue	765
shale sdy	800
shale	835
shale sdy	840
lime, shale	855
sand	988
Total depth	

Tops:

Codell sand	70
Dakota sand	645
Cheyenne sand	855

855-875 good porosity
880-885, fair porosity
928-940, good porosity
940-950, poor porosity
950-970, good porosity