

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: L-K Wireline, Inc.  
Address: PO Box 1188 Hays, KS 67601  
Phone: (785) 625-6877 Operator License #: 5453  
Type of Well: SWD Docket #: E16334-001  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 2/28/05 (Date)  
by: Herb Deines (KCC District Agent's Name)  
Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No  
Producing Formation(s): List All (If needed attach another sheet)  
N/A Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-163-01537  
Lease Name: Bedard  
Well Number: #2 SWD  
Spot Location (QQQQ): C - NE - SW - NW  
1650 Feet from ☒ North / ☐ South Section Line  
660 Feet from ☐ East / ☒ West Section Line  
Sec. 18 Twp. 9 S. R. 18 ☐ East ☒ West  
County: Rooks  
Date Well Completed: 1/30/64  
Plugging Commenced: 2/25/05  
Plugging Completed: 2/28/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Water	3497	3950	8-5/8	215	-----
Granite Wash	Water	3950	3960	5-1/2	3497	-----

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tbg. to 3000', spotted 150 sx 60/40 poz-mix w/ 500# hulls, pulled tbg. to 1500' circulated cement w 100 sx 60/40 poz-mix w/300# hulls. Pulled tbg. Tied to annulus mixed 50sx 60/40 poz-mix @ 350#, shut in @ 100#. Mixed 25sx down 5-1/2 casing @ 500# Shut in @ 50#

Perfs @ 1475' and 850' 3 each


Name of Plugging Contractor: Allied Cementing, Inc. License #: \_\_\_\_\_

Address: PO Box 31, Russell, KS 67665-0031

Name of Party Responsible for Plugging Fees: L-K Wireline, Inc.

State of Kansas County, Ellis, ss.

Randy K Longpine, President - L-K Wireline Inc. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the



(Signature) [Signature]  
(Address) PO Box 1188

SUBSCRIBED and SWORN TO before me this 15 day of March, 20 05  
Charlotte Weber My Commission Expires: 12-28-07  
Notary Public