

# D & D DRILLING COMPANY, INC.

SCHWEITER BUILDING

WICHITA 3, KANSAS

PHONE AM 5-0611

GLENN M. DUNN, JR.

JAMES R. DANIELS

## COMPLETION REPORT

Bedard #2  
N/2 SW NW  
Section 18-9S-18W  
Rooks County, Kansas

Elevation: 2077 K.P.  
Rotary Total Depth - 3503'  
5 1/2" pipe set at 3497'  
Zero point 6.24' above Braden Head

1-15-64 Moved in & rigged up Bill Hay Drilling Company, Rig #1 Cardwell  
spudder. Swabbed hole down and clean up. Drilled baffle ring &  
rubber plug. Shut down till morning.

1-16-64 Started up at 7:00 AM, drilled 35' cement and Packer shoe. Ran  
bailer full of mud & oil (no water). Ran bailer recovered bailer  
full mud and oil - filled up approximately 70' in 30 min. Ran bailer again  
recovered bailer full mud & heavy oil fill up at 80' in 40 min. Ran bailer  
to clean out mud, recovered bailer full froggy oil fill up still same in  
50 min. Railed for 5 hours bailing out approximately 3 barrels per hour  
getting 1/2 gal. of mud each run. Fluid level raised to 150' in 4 hours.  
Dumped 50 gal. mud acid down casing and let set overnight.

1-17-64 Started up at 7:00 AM checked fluid level at 900' off bottom.  
Swabbed hole down to 3150' recovered 13 barrels oil, no water.

Started swab test as follows at 3150'

9:30 to 10:30	2.71 bbls	no water
10:30 to 11:30	2.27 bbls	no water
11:30 to 12:30	2.17 bbls	no water
12:30 to 1:30	1.62 bbls	no water
1:30 to 2:30	1.08 bbls	no water

Swabbed down to approximately 3300'.

2:30 to 3:15	3.52 bbls	no water
3:15 to 4:15	2.17 bbls	no water

Swabbed hole down to acidize, recovered 4.89 bbls. Acidized with 250 gals.  
XXM38 by Dowell 250# max. pressure injection rate oil bbl per min. Pressure  
dropped to 50# in 2 min, to 0# in 5 min. Shut in at 7:30 PM.

1-18-64 Started up at 7:00 AM found fluid 300' down. Swabbed hole down to  
3000' recovered 73 bbls of load oil (total load 92 bbls) Tested at 3000' for  
1 hour recovered 3.25 barrels. Dropped down to 3400' recovered 8.68 bbls oil.  
Pulled Swabb every 1/2 hour as follows:

Completion Report

Bedard No. 2

Page No. 2

10:05 to 10:35	4.34 bbls	no water	load back
10:35 to 11:05	3.25 bbls	no water	
11:05 to 11:35	2.71 bbls	no water	
11:35 to 12:05	2.71 bbls	no water	
12:05 to 12:35	2.17 bbls	no water	
12:35 to 1:05	1.08 bbls	no water	
1:05 to 1:35	1.08 bbls	no water	
1:35 to 2:05	1.62 bbls	no water	
2:05 to 2:35	1.62 bbls	no water	
2:35 to 3:05	2.17 bbls	no water	
3:05 to 3:35	1.62 bbls	no water	

Ran bailer recovered bailer full oil no water.  
Tore down cable tools.

1-21-64 Found fluid at 2300' when ran rods.

D & D Drilling Company, Inc.

J. J. Wenrich