

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-163-05966

Company- MALLONEE DRILLING CO.
Farm- Benedick No. 1

SEC. 1 T. 9 R. 187
SE SE NW

Total Depth. 3530'
Comm. 4-29-56 Comp. 5-27-56
Shot or Treated.
Contractor. Mallonee Drlg. Co.
Issued. 6-30-56

County Rocks
KANSAS



CASING:
8 5/8" 125' cgm w/55 sx

Elevation. 2030' DF

Production. Dry

Figures indicate Bottom of Formations.

post rock	20
grey shale	100
blue shale	125
shale and shells	800
sand and shale	1100
shale and shells	1390
anhydrite	1425
lime and shale	1445
shale and shells	2010
shale	2145
lime and shale	2560
lime and red bed	2700
lime and shale	3198
lime	3339
lime and shale	3530
Total Depth	

Tops:	
Topeka	2941
Heebner	3163
Lansing	3208
Conglomerate	3466
Arbuckle	3490

DST #1 3355-3392', open 30 mins., weak blow
for 15 mins, rec. 32' watery mud. BHP 990#.
no flow pressure.