

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

15-163-03474


Company - SINCLAIR PRAIRIE OIL CO.
Farm - A. Bedard No. 1

SEC. 18 T. 9 R. 18 W
NW 1/4 NW
330' FNL & 330' FWL NW 1/4

Total Depth. 3566'
Comm. 10-24-46 Comp. 11-11-46
Shot or Treated.
Contractor. Harbar Drlg. Co. (Rot.)
Issued. 6-21-47

County. Rocks

KANSAS



Elevation. 2085 SCH & RB

Production. Dry

CASING:

10 3/4" 1436'
5 1/2" 3541'

Figures Indicate Bottom of Formations.

sand & surface clay	100
shale & shells	250
lime & shale	340
shale & shells	540
sand & shale	770
shale	860
lime & sand	940
sand & shale	1185
shale & iron	1225
red rock	1280
shale & shells	1430
anhydrite	1460
red bed	1510
shale & shells	1950
shale	1970
lime	2220
lime brkn	2350
lime	2720
lime & shale	2785
shale	2815
lime & shale	2950
lime	2995
lime & shale	3075
lime	3180
shale & lime	3230
lime	3260
chert & lime	3285
lime	3495
lime & shale	3530
conglomerate	3519
Simpson	3540
Lime Arbuckle	3566
Total Depth.	

Tops: RF	
Lansing-K.C.	3263
Base Kans. City	3488
Conglomerate	3513
Simpson	3518
Arbuckle	3541

Drl'd. cem. plug, dry when drlg. @ 3559'
Drl'd. 3566' in Arb. cleaned out 3555' dry
(1/4 BWPH @ 3566')
Set Plug 3500' Perf. 18 holes in K. C.
3444-61'
Swab 8 hr. 4 1/2 BWPH, no oil
Set plug 3443' Perf. 5 holes 3416-21'
swab 11 BWPH
Set plug 3407' Perf. 12 holes 3337-48'
swab 12 BWPH
Set plug 3330' Perf. 6 holes 3296-3301'
Swab 21 BPH wtr.
Dry Hole.