


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-163-041012
 SEC. 19 T. 9 R. 18W
 SE SE SE

Company- CONTINENTAL OIL COMPANY
 Farm- Gilbert No. 1

County Rooks
 KANSAS

Total Depth. 3626
 Comm. 2-23-53 Comp. 3-5-53
 Shot or Treated.
 Contractor. Garvey Drlg. Co.
 Issued. 5-2-53



CASING:

10 3/4" 202' cem. w/150 sx
 5 1/2" 3620' cem. w/200 sx

Elevation. 2188
 2186(m)

Production. 36 BO & 4 BW 24 hrs.

Figures Indicate Bottom of Formations.

surface soil	40
sand	150
shale blue	630
sand	730
shale	850
sand	1260
red bed	1375
red bed & shale	1540
anhydrite	1570
shale & shells	1975
shale & salt	2180
lime & shale	2490
shale	2530
lime & shale	2725
lime	2760
lime & shale	3325
lime	3560
conglomerate	3575
lime	3583
conglomerate	3611
lime	3623 RTD
lime	3626
Total Depth	

Tops:

Heebner	3322
Toronto	3344
Lansing	3365
Arbuckle	3619