

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-163-03273


Company- SINCLAIR OIL CO.
Farm- J. Hilgers No. 1

SEC. 19 T. 9 R. 18W
SW SW NW
330' fr Sth & W. lines NW/4

Total Depth. 3596
Comm. 2-23-52 Comp. 3-4-52
Shot or Treated.
Contractor.
Issued. 6-7-52

County Rooks

KANSAS



Elevation. 2172 D.F.

Production. Temp. allowable
25 bbls.

Figures Indicate Bottom of Formations.

sand, shale, shells	314
redbeds & sand	954 drlg. 9" hole
sand, shale, shells	1370
redbeds, shale, shells	1545
anhyd.	1595
shale, shells, lime	2084
sdv shale, lime strks	2310
shale, lime	2543
lime brkn	2673
shale, lime	2798
lime brkn	2930
lime & shale strks	3038
lime brkn	3168
lime & shale strks	3208
lime brkn	3263
lime & shale strks	3353
lime & shale	3420
lime & shale strks	3496
lime	3591 RTD
lime	3596
Total Depth	

Tops: Sample	
Topeka	3097 G.L.M.
Lansing	3343
Arb.	3583

Ran Sch. 3-4-52

Drilled com & shoe, cleaned out to T.D.
3591 Showed 12 gals. oil per hr.
3-11-52 Az. w/1000 gls.
Starting press. 100# Max. press 1000 #.
Completion press. 700# Loaded hole
146 bbls. wtr.
Rec. acid load, & swb 122 bbls. oil no
wtr in 22½ hrs. averaging 5 bbls. oil an
hr.
Temp. allowable 25 bbls daily filed to
be effective 3-11-52

Surface level meas. on formation.
R.B. to G.L. was 5'
Zero point top R.B. to top 7" spider was
8'