

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-163-01546

Company- HEATHMAN-SEELIGSON DRILLING CO.
Farm- Baumgartner "B" No. 2

SEC. 20 T. 9 R. 18W
C NE NW NE

Total Depth. 3590
Comm. 12-30-53 Comp. 1-10-54
Shot or Treated.
Contractor. Heathman-Seeligson Drilling Co.
Issued. 2-27-54

County Rooks
KANSAS



CASING:

8 5/8" 163,99' cem. w/105 sx
5 1/2" 3585' cem. w/100 sx

Elevation. 2170' DF

Production. 3000 BO & NW

Figures indicate Bottom of Formations.

surface hole	170	
shale & sand	680	
red bed, shale & sand		1060
sand	1235	
shale & shells	1505	
anhydrite	1555	
shale & shells	2035	
shale & lime	2305	
shale & sandy lime	2425	
shale & lime	3092	
lime	3302	
shale	3305	
lime	3590	
Total Depth		

TOPS: (KB)

Anhydrite	1505
Topoka	3092
Hoboken	3302
Toronto	3322
Lansing-KC	3342
Arbuckle	3582

DRILLING-IN DATA:

Drilled plug; cleaned out to TD 3588;
Bailed 1 BOFH.
Drilled Deeper 2' to 3590' TD
Bailed 10 1/2 BOFH-4 hrs.
Acidized w/500 gal. @ 300# pressure;
finished on vacuum.
Sped 38 BOFH ofr 2 hrs. 1500' off
bottom, no wtr.
Put on pump.