

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY

508 E. Murdock, Wichita, Kansas

Company - CITIES SERVICE OIL CO

Farm - Wildrix

No. 1

SEC. 3

T. 9

R. 18W

SW SW NW

330' N & 330' E W/4 Corner

Total Depth. 3374' SLM P.B. 3315 SLM

Comm. 7-14-49

Comp. 7-22-49


Shot or Treated. 3000 gals.

Contractor. Braden Drlg. Co.

Issued. 11-5-49

County. Rooks

KANSAS



Elevation. 1984 2nd

Production. 160 oil, 53 wtr, 24hrs

Figures Indicate Bottom of Formations.

surface soil	5
shale	80
shells	100
shale sdy	180
shale	260
shells	286
shale & shells	470
red bed & sand	870
sand	1150
shale & sand	1240
red bed & shale	1355
shale	1360
anhyd.	1393
shale	1575
shale & shells	2050
shale & lime	2285
lime & shale	2475
shale & lime	2775
shale	2970
lime & shale	3065
lime	3170
lime brkn	3215
lime	3297
lime brkn	3535
lime	3570

3370 RTD = 3374 SLM

Tops:

Corr. Lansing 3169

Pen 205

Drilled com to 3365 SLM

Perf. 53 shots 3337-53

7-28-49 Acidiz d 500 gals. 3337-53

Bailed 5 gals. oil & 14 gals. wtr per
hr for 12 hrs.

Set Lane-Wellis plug at 3322 SLM

Perf. 63 shots 3246-63 $\frac{1}{2}$

" 12 " 3234-40

53 gals. oil & 52 gals. wtr 11 hrs.

Dumped 1 sack CalSeal on plug; top
CalSeal 3315 SLM.7-31-49 Acidized 2500 gals. 3234-63 $\frac{1}{2}$

8-1-49 Pumped 150 oil, 136 wtr, 20 hrs.