

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


15-1103-03825

Company - W. L. Hartman
B. & R. DRILLING CO.
Farm - Rempe No. 1

SEC. 21 T. 9 R. 18 W
NW 1/4 SE

Total Depth. 3592'
Comm. 1-10-47 Comp. 1-24-47
Shot or Treated.
Contractor.
Issued. 6-21-47

County. Rocks
KANSAS



CASING:
8 5/8" 169' Cem. w/125 sx.
5 1/2" 3579' Cem. w/100 sx.

Elevation. 2166 act. & sh

Production. Pot. 1470 BO.

Figures indicate Bottom of Formations.

surface clay	15
shale & shells	169
shale wh	235
shale	890
sand	1000
shale & shells	1050
sand	1170
shale & shells	1350
sand	1385
shale, shells & iron	
ctrks	1497
anhydrite	1541
shale & shells	1790
shale, shells & salt	1975
anhydrite & shale	2070
lime & shale	2715
lime	2820
lime brkn	2850
lime & shale	3075
lime	3125
lime brkn	3205
lime & shale	3255
lime	3515
lime & shale	3578
Arbuckle lime	3581

Corr. to Rot. table
3581=3579

lime 3592
Total Depth.

Tops:
Topeka 3076
Heebner 3286
White Lime 3300
Lansing 3325
Arbuckle 3576