

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - W. L. HARTMAN
Farm - Weidman

No. 1

15-163-01567
SEC. 21 T. 9 R. 18 W
CE/2 SE SW

Total Depth. 3577'

Comm. 5-13-47

Comp. 5-26-47

Shot or Treated.


Contractor.

Issued. 8-9-47

County.

Rooks

KANSAS



CASING:

8 5/8"
5 1/2"

166' Cem. w/100 sx.
3573' Cem. w/75 sx.

Elevation. 2170' b
2168' sch

Production. Pot. 3000 BO

Figures Indicate Bottom of Formations.

surface clay & shale	40
shale	85
sand & shale	135
shale & shells	166
lime (chalky, sft)	230
shale	510
shale sdy & sand	750
sand & shale	1185
shale, sand & pyrite	1303
shale & lime shells	1330
shale & shells	1500
anhydrite	1530
shale & shells	1735
shale & lime shells	1945
lime sdy, shale & shells of pyrite	1975
lime & shells of pyrite	2050
lime & shale	2160
red bed, shale & shells	2206
lime & shale	2275
lime	2340
lime & shale	2490
lime brkn	2685
lime & shale	2940
lime brkn	2960
shale & lime	3220
lime	3240
lime & shale	3330
lime K. C.	3385
lime	3570
lime brkn	3577
Total Depth.	

Tops: DF

Topeka	3078
Heebner	3288
White Lime	3305
Lansing	3330
Arbuckle	3576