

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas


Company - STANOLIND OIL AND GAS COMPANY  
Farm - Wm McConchie No. 1

SEC. 27 T. 9 R. 18W  
SW SW NW  
330' SN1 & 330' WE1 NW $\frac{1}{4}$

Total Depth. 3592'  
Comm. 11-30-47 Comp. 12-24-47  
Shot or Treated. Acid.  
Contractor.  
Issued. 2-14-48

County. Rooks

KANSAS



Elevation. 2146 *ft.*

Production. 167 BO

CASING:

13" OD 142' Cem. w/200 sx  
5 $\frac{1}{2}$ " OD 3589' Cem. w/650 sx

Figures indicate Bottom of Formations.

cellar 0-11  
water sand 80  
shale & shells 650  
shale & sand 1515  
anhydrite 1545  
shale & lime 2830  
shale & shells 3030  
shale & lime 3100  
lime 3324  
lime 3365  
Core #1 shale & lime 3375  
lime 3418  
Core #2 lime 3428  
DST at 3426' recovered 610'  
mud cut oil & no water in one  
hour through  $\frac{1}{2}$ " choke gravity  
of crude recovered was 32.

lime 3576  
lime 3589

Core #3 full recovery of  
Dolomite, gy medium to coarse  
xylm w/spotted heavy blk oil  
& show of water 3591  
DST 3591' recovered 30' water  
in one hour through  $\frac{1}{2}$ " choke  
Drilled plug to 3591 & dolomite  
to 3592', no fluid in hole  
dolomite 3592  
Total Depth

Tops:

Anhydrite 1515-1545  
Topeka 3063-3100  
Lansing 3322-3365  
Arbuckle 3587-3592