

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

15-163-02333


Company CITIES SERVICE OIL COMPANY
Farm Slason No. 1

SEC. 27 T. 9 R. 18W
NW c SW
330' S & 330' E of W/4 c

Total Depth. 3660' SLM PB 3444'
Comm 9-20-47 Comp. 10-1-47
Shot or Treated. Acidized
Contractor. R.W. Rine Drilling Co.
Issue 1-31-48

County. Rooks

KANSAS



Elevation. 2150 Ind.

Production. Physical Potential:
231 oil, 53% water, 24 hr.

CASING:

8-5/8" 1508' cem. w/750 sx
5-1/2" 3660' cem. w/150 sx

Figures indicate Bottom of Formations.

shale & sand	0-850
shale & shells	1020
sand	1220
lime & shale	1265
shale & shells	1488
anhydrite	1535
shale & shells	2175
shale & lime	2480
shale & shells	2960
shale & lime	3215
lime & shale	3300
lime	3416
lime & shale	3465
lime & chert	3474
cherty lime	3480
lime	3545
lime & shale	3605
lime	3660

3660 Rot. TD 3660 SLM

Total Depth

Plugged back to 3444'

Tops:

Lansing	3320
Arbuckle	3603
Penetration	57

Drilled cement to 3624

Perf. 28 shots	3476-88
Perf. 48 shots	3400-14

Acidized 1000 gals 3476-88
Pumped 24 oil, 289 water, 20 hrs.

Set Lane-Wells plug at 3451

Dumped 1 sack cement on plug; top
of cement 3444

Acidized 2000 gals. 3400-14