

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


15-163-01574

Company - SKELLY OIL COMPANY
Farm - Ernest J. Rempe No. 1

SEC. 28 T. 9 R. 18W
NWc NE
330' fN1, 330' fW1 NE $\frac{1}{4}$

County. Rooks

KANSAS



Elevation. 2165 sea + Rb

Production. Pot. 259 BO

Total Depth. 3597'
Comm. 3-21-47 Comp. 4-9-47
Shot or Treated. Acid w/3000 gals. between 3595-3597'
Contractor. H. and T. Drilling Co.
Issued. 9-13-47

CASING:

13" OD 175' Cem. w/150 sx
8-5/8" OD 1496' Cem. w/450 sx
5-1/2" OD 3395' Cem. w/200 sx

Figures Indicate Bottom of Formations.

surface soil, clay & sand	0-60
sand, clay & shale	185
red bed & shale	680
shale	800
shale & shells	1030
shale	1135
shale	1260
shale, red bed & pyrites	
of iron	1365
red bed	1488
anhydrite & lime	1496
lime	1565
shale	1840
shale & shells	1995
lime & shale	2250
lime	2300
lime & shale	3085
lime	3341
lime gy oolitic	3344
lime	3380
lime gy oolitic	3389
lime	3405
lime gy oolitic	3418
lime	3530
lime & shale	3580
lime	3594
dolomite med. hrd brwn	3595
dolomite brwn sft	3597
Total Depth	

Tops:
Anhydrite 1488
Lansing Lime 3341
Arbuckle Lime 3594

3341-3344 Sli. por & stain
3380-3389 Sli. por. & lt sat.
3402-3418 Sli. por. and stain
3594-3595 Sli. por. and stain
3595-3597 Porous and saturated.

April 26 shot 300 qt 3595 - 3597