

State Geological Survey
WICHITA, BRANCH

DRILLERS' WELL LOG

15-163-20625
28-98-18W

DATE COMMENCED: July 26, 1976
DATE COMPLETED: August 1, 1976

R & R Oil
REMPE # 6
C N/2 NE/4
Sec 28-T9-R18W
Rooks County, Kansas

ELEVATION: 2164 K.B.

0 - 225' Clay and Shale
225 - 1485' Shale and Sand
1485 - 1524' Anhydrite
1524 - 2075' Shale
2075 - 3093' Shale and Lime
3093 - 3306' Lime
3306 - 3310' Shale
3310 - 3327' Lime and Shale
3327 - 3348' Lime
3348 - 3575' Lime
3575 - 3614' Lime, Shale, Chert
3614' RTD

FORMATION TOPS

Anhydrite	1485
Topeka	3093
Heebner	3306
Toronto	3327
Lansing K.C.	3348
Base K.C.	3575
RTD	3614

SURFACE PIPE:

Set used 8 5/8", 28# pipe
@ 225' w/140 sacks Common,
2% Gel, 3% cc.

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 3rd day of August, 1976.

Vereddy M. Hague
Notary Public

My Commission Expires: April 11, 1978