

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-163-00639

Company. HEATHMAN & COMPANY
Farm. Jelinek No. 1

SEC. 30 T. 9 R. 18W
NW NE NE

Total Depth. 3617
Comm. 11-25-52 Comp. 12-7-52
Shot or Treated.
Contractor.
issued. 1-17-52

County Rooks
KANSAS



Elevation. 2196 RB

Production. 149 BO & NW 18 hrs.

Figures indicate Bottom of Formations.

post rock & shale	60
shale blue & shells	136
shale & clay	265
shale & red bed	850
sand & shale	990
sand	1200
sandy lime	1240
shale, shells & redbed	1530
red bed & shale	1551
anhydrite	1590
shale & shells	1950
lime & shale	2735
lime	2840
lime & shale	3117
lime	3585
conglomerate	3612
arbuckle	3614
arbuckle	3617
Total Depth	

Tops:	
Topeka	3116
Heebner	3326
Toronto	3348
Lansing	3367
Base-Kansas City	3570
Arbuckle	3608

DST: 3446-3400' tool open
1 hr. 14 mins. rec. 90'
slightly oil cut mud. 120'
heavy oil cut mud. 300' gas
cut oil. 300' water & gas
cut mud 240' salt wtr BHP 15 min.
990#.

DST: 3530-3545' tool open 1 hr.
15 mins. rec. 1920' of fluid
10% oil 90% wtr and mud. BHP 15 min.
1010#.

DST: 3609-3614' tool open 1 hr.
and 15 mins. rec. 130' free oil
90' very heavy oil cut mud.
BHP 15 min. 740#.

Schlumberger log run to T.D.

Note: All measurement Rotary
Bushing.