

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-163-01580

Company- HEATHMAN & COMPANY
Farm- Jelinek No. 2

SEC. 30 T. 9 R. 18W
NE NE NE

Total Depth. 3658
Comm. 5-5-53 Comp. 5-15-53
Shot or Treated.
Contractor. Strain Drilling Co.
Issued. 12-17-55

County Rooks
KANSAS



CASING:

8 5/8 @ 153' w/ 110 sx cmt.
5 1/2 @ 3657' w/ 100 sx cmt.

Elevation. 2195 RB

Production. 348 BOPD, NW

Figures indicate Bottom of Formations.

clay & sand	40
blue shale & shells	151
shale	465
shale & shells	665
sandy shale	740
shale & shells	850
sand & shale	1010
sand	1260
shale, shells & red bed	1515
red bed & shale	1540
anhydrite	1582
shale & shells	1800
lime & shale	3380
lime	3560
lime & shale	3580
lime	3605
Arbuckle	3658
Total Depth	

TOPS:

Anhydrite	1540
Topeka	3113
Heebner	3323
Toronto	3344
Lansing	3363
Arbuckle	3604

Ran Schlumberger Log

All RB Meas.

DST #1: 3368-3410, open 30 min. rec.
15' drlg. mud, w/ sl. show oil, BHP
540#/15 min.

DST #2: 3441-54, open 1 hr. rec. 125'
HOCM, 150' wtr. BHP 1100#/20 min.

DST #3: 3514-25, open 30 min. very
weak blow 3 min. rec. 6' rotary mud,
BHP 780#/15 min.

DST #4: 3555-71, open 30 min. rec.
8' rotary mud, wk. blow 10 min. BHP
480#/15 min.

DST #5: 3604-20, open 1 hr. rec.
270' free oil, 180' HOCM, FP 195#,
BHP 780#/26 min.

DST #6: 3620-40, open 45 min. rec.
330' HOCM, 445' clean oil, strong
blow thruout, FP 300#, BHP 770#/15 min.

DST #7: 3640-55, open 45 min. rec.
1670' SW, strong blow thruout, BHP
1020#/15 min.