

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-163-00549

Company- BIRMINGHAM-BARTLETT DRILLING CO.
Farm- Yohe "A" No. 1

SEC. 4 T. 9 R. 18W
SE SW SE

Total Depth. 3624
Comm. 9-28-53 Comp. 10-10-53
Shot or Treated.
Contractor. Birmingham-Bartlett Drilling Co.
Issued. 10-31-53

County Rooks
KANSAS



CASING:
8 5/8" 153' cem. w/125 sx

Elevation. 2042 RB.

Production. Dry

Figures Indicate Bottom of Formations.

shale	153
shale & shells	1000
sand & shale	1100
shale & shells	1140
red bed & shells	1395
anhydrite	1435
shale & shells	1935
brkn lime	2080
lime & shale	2845
shale & shells	2975
lime & shale	3060
lime	3402
lime & shale	3505
Conglomerate	3624
Total Depth	

TOPS:
Anhydrite 1395
Topeka 2962
Hoebner 3175
Toronto 3196
Lansing 3215
Cherty Conglomerate 3472

D.S.T. #1 3240-60 Open 1
hr., rec. 95'
mud. 1100# BHP
D.S.T. #2 3283-3308 open
1 hr., rec.
1380' wtr, 1040#
BHP
D.S.T. #3 3308-33 open 1
hr., rec. 1140'
wtr 1020# BHP
D.S.T. #4 3364-3400 open
20 min., rec.
60' mud. 1120#
BHP