

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY

508 E. Murdock,

Wichita, Kansas

15-163-03350

Company - SKELLY OIL CO.

Farm - J. W. Yohe

No. 1

SEC. 4 T. 9 R. 18W

NE NE SE 330' fr NL

330' fr EL SE/4

Total Depth. 3467 PB 3280

Comm. 5-24-49

Comp. 6-6-49


Shot or Treated. Acid

Contractor. Claude Weintworth Drlg.

Issued. 10-15-49

County. Rooks

KANSAS



CASING:

8 5/8" 1357' cem. w/550 sx.

5 1/2" 3466' cem. w/200 sx.

Elevation. 1999 2nd

Production. 87 bbls.

Figures Indicate Bottom of Formations.

surface soil & sand	100
shale & sandstone	400
shale & shells	900
sand	1075
shale & shells	1357
anhyd.	1376
Reamed 9 7/8" hole to	12 1/2"
anhyd.	1390
shale	1440
shale & shells	1510
shale	1790
salt	1830
shale	2000
lime brkn	2355
shale	2495
lime & shale	3045
lime	3270
lime	3414
lime & shells	3450
lime	3464
dolo. lgt gry to buff	
coarsely xyn. to dense	3467
Total Depth P.B.	3280

Tops:

Anhyd.	1362
Heobner shale	3140
Toronto lime	3162
Lansing lime	3179
Congl.	3436
Arbuckle lime	3464

Fair oil saturation 3162-3167

Pin-point por. fair oil sat. 3215-3223

Fair por., fair to poor sat. 3251-3267

6-29-49 1st acid treatment

300 quarts 3449-3453

7-1-49 300 gals. 3449-3453

7-5-49 500 gals. 3251-3260

7-9-49 1000 gals 3215-3223

By Dowell Inc.

Producing formation Lansing lime

3215-3260

POB 8 hrs. 29.02 BO 6 BW to estab. 24

hr. SCC pot. of 87 bbls.