

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
 412 Union National Bk. Bldg. Wichita, Kansas


15-103-02290

Company - ANDERSON-PRICHARD OIL CORP.  
 Farm - Cabbage No. 7

SEC. 7 T. 9 S. 18W  
 CN/2 NE/4 SW/4

Total Depth. 3469'  
 Comm. 4-23-48 Comp. 5-5-48 ✓  
 Shot or Treated. Acidized  
 Contractor. Goodmaster Drlg. Co.  
 Issued. 9-11-48

County. Rooks KANSAS



CASING:

8 5/8" 211' Cem.  
 5 1/2" 3469' Cem.

Elevation. \_\_\_\_\_

Production. 311 Bbls. oil  
 no water

Figures Indicate Bottom of Formations.

surface	40
shale and shells	700
redbed and shale	775
shale and shells	895
shale and sand	930
sand	1150
shale and redbed	1340
shale and shells	1430
anhydrite	1460
shale and shells	1905
lime and shale	2975
lime	3045
lime, brown	3140
lime and shale	3240
lime	3469
total depth	

Tops:  
 Heebner 3184'  
 Lansing 3224  
 Simpson 3463  
 Arbuckle 3468

T.D. 3472 = 3470 SLM

Dst 3306-15 Open 1/2 hr,  
 rec. 265' wtr & oil cut mud  
 Acid: 500 gals. Swabbed  
 18 BOPH 6 hrs., no water.