

F-103-21195  
16-9-18W

CONTRACTOR'S WELL LOG

State Geological Survey  
WICHITA, BRANCH

OPERATOR:	Zenith Drilling Corporation
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	KABA #1
LOCATION:	NE NE NW, Section 16-9S-18W Rooks County, Kansas
SPUD DATE:	12/20/80
COMPLETION DATE:	12/24/80

0	1417	Sand & Shale
1417	1453	Anhydrite
1453	1995	Sand & Shale
1995	2842	Shale & Lime
	2842	Rotary Total Depth

Spud @ 12:45 p.m., 12/20/80. Drilled 247' in a 12 1/4" hole. Ran 6 jts. of 8 5/8" - 20# casing (tally 237.21) Set @ 243.71'. Cemented with 175 sx. of common 2% gel, 3% c.c. Plug was down @ 7:15 p.m., 12/20/80. Cement did circulate.

. 2842' Set 1st Plug @ 720' with 70 sx., 2nd plug Set @ 240' with 25 sx., Set 3rd Plug @ 40' solid bridge with 10 sx.; Rathole 5 sx., 50-50 posmix, 6% gel. Plug was down @ 7:00 a.m., 12/24/80. State Plugger - Marion Schmidt. .

SAMPLE TOPS:

A	drite	1417'
B	hydrite	1453'

STATE OF KANSAS     )  
                          )   SS  
COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary/Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the KABA #1, NE NE NW, Section 16-9S-18W, Rooks County, Kansas.

ABERCROMBIE DRILLING, INC.

*(Handwritten signature)*