

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

500 East Murdock,

Wichita, Kansas

15-163-02310

Company- CITIES SERVICE OIL CO.
Farm- Kaba No. 3

SEC. 16 T. 9 R. 18W
NE SE SE
1650'S & 330' W of E/4c

Total Depth. 3553
Comm. 9-18-53 Comp. 10-1-53
Shot or Treated.
Contractor. R. W. Rine Drilling Co.
Issued. 12-19-53

County Rocks

KANSAS



Elevation. 2141

Production. Pot. 296 B0, 65 B1

CASING:
8 5/8 @ 235' w/ 150 sx cmt/
5 1/2 @ 3550' w/ 175 sx cent.

Figures indicate Bottom of Formations.

sand & clay	235
shale & shells	680
shale & mod bed	840
shale & red bed	1460
anhydrite	1500
shale	1730
shale & shells	1950
shale & lime	2145
shale & shells	2350
lime & shale	3255
lime	3414
lime & shale	3495
lime	3505
lime & shale (SLM 3552)	3556
lime	3553
Total Depth	

TOPS: (corr.)	
Heebner	3261
Dodge	3282
Lansing	3301
Arbuckle	3549
Penetration	4

FU
85' in 20 min @ 3552
500' in 1 hr. 15 min. @ 3553
800' in 1 hr. 45 min.
1223' in 2 hrs. 45 min.
1988' in 8 hrs. 45 min.