


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CONTINENTAL OIL CO.
Josephine Gick No. 2.

SEC. 1 T. 9 R. 19 W
SWc SW
330' N 330' E SW Cor.

County. Rocks



Total Depth. 3467'
Comm. 8-12-43 Comp. 8-31-43
Shot or Treated.
Contractor. Parker Drilg. Co.
Issued. 10-30-43

CASING:

10³/₄" 238' Cem.
6" 3448' Cem.

Elevation.

Production. Phy. Pot. 267 B.
No wtr

Figures Indicate Bottom of Formations.

surface clay	0-40
surface sand	85
shale	500
sand & shale	842
shale	862
sand & shale	1100
red bed & shale	1260
red bed & sand strks	1365
red bed & shale	1410
anhydrite	1460
shale	1500
red bed & shale	1590
shale & shells	2069
shale & lime	2300
lime	2320
shale & lime	2430
shale	2450
lime & shale	2590
lime & shale strks	2675
lime & shale	3129
lime	3467
Total Depth.	

Top Arbuckle Lime 3448

8-30-43 drld out cement plug
& hole filled 2700' w/oil
in 2 hrs - deepened to 3465
9-1-43 estb. 24-hr phy. pot.
of 267 bbls oil, no wtr
Total Depth 3466 in Arbuckle
Lime

Note: All above footages,
except formation record,
are calculated from the
cement floor level