

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas


15-163-09400

CONTINENTAL OIL CO.  
Dan Barry "A" No. 2.

SEC. 2 T. 9 R. 19 W  
NE SW SE  
990'N 990'E S $\frac{1}{2}$  Cor.

Total Depth. 3451' (3450' Cem. Fl. Lev.)  
Comm. 7-2-43 Comp. 7-28-43  
Shot or Treated.  
Contractor. Parker Drlg. Co.  
Issued. 9-4-43

County. Rocks



CASING:  
10 $\frac{3}{4}$ " 240' Cem.  
6" 3455' 6" ? Cem.

Elevation.

Production. Echo. Pot. 3000 B.

Figures Indicate Bottom of Formations. No wtr, Ind. Cap. 116,000 B.

surface soil & sand	0-185
shale & shells	250
shale	400
sand	510
anhydrite & shale	650
sand	810
shaley sand	875
sand sft	1120
sand & shale	1410
anhydrite	1440
red bed & shale	1500
shale & shells	1890
shale	2000
lime & shale	2240
shale & shells	2505
shale sticky	2585
lime & shale	2940
lime	2965
shale	2985
lime	3060
lime & shale	3120
lime	3365
lime & shale	3451
Total Depth.	

Top Arbuckle Lime 3432  
7-23-43 drld cement plug  
& hole filled 2600' w/oil  
in 30 minutes  
7-26-43 swbd 60 BOPH for  
5 hrs - unable to lower  
fluid  
7-28-43 Estb. an Echo. Pot.  
of 3000 BO, no wtr. Well  
has an indicated capacity  
of 116,000 BO

Total Depth 3450 in  
Arbuckle Lime

Note: All above footages  
except formations, are  
calculated from cement  
floor.