


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CONTINENTAL OIL CO.
Dan Barry "A" No. 3.

SEC. 2 T. 9 R. 19 W
NE NW SE
330'S 990'E Center

Total Depth. 3443' (DF 3442')
Comm. 7-29-43 Comp. 8-17-43
Shot or Treated.
Contractor. Parker Drlg.Co.
Issued. 10-23-43

County. Rocks



CASING:
10³/₄" 239' Cem.
6" 3430' Cem.

Elevation.

Production. Pot. 3000 B.
Echo.

Figures Indicate Bottom of Formations.

surface soil & sand	0-50
shale & shells	250
shale & shells	460
sand & shells	1100
red bed & pyrite iron	1260 ✓
shale & shells	1374
shale & pyrite iron	1395 ✓
anhydrite	1450
red bed & shells	1635
shale & shells	1926
shale & lime	2055
shale & lime shells	2205
shale & shells	2293
lime w/shale strks	2380
lime	2410
lime & shale	2585
lime	2655
lime & shale	3065
lime	3420
shale	3431
lime	3434
lime	3443
Total Depth.	

Top of Arbuckle Lime 3430
8-15-43 drld out cement plug
& hole filled 2700' w/oil in
30 minutes
8-19-43 Estb. an Echo.Pot. of
3000 BO, daily
Total Depth in Arbuckle Lime
formation 3442

Note: All above footages are
calculated from cement floor
level, except formation red