


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - CONTINENTAL OIL CO.  
Farm - Dan Barry "A" No. 4.

15-1103-09402  
SEC. 2 T. 9 R. 19 W  
N E c SE  
330'S 330 W E  $\frac{1}{2}$  Cor.

Total Depth. 3450' (CPL 3449)  
Comm. 11-26-43 Comp. 12-18-43  
Shot or Treated.  
Contractor. Parker Drlg. Co.  
Issued. 3-4-44

County. Rocks  
KANSAS



Elevation. \_\_\_\_\_

Production. Deptho. Pot. 2911 B.  
No wtr

CASING:  
10  $\frac{3}{4}$ " 240' Cem.  
6" 3434' Cem.

Figures Indicate Bottom of Formations.

shale & part rock	0-165
shale & shells	700
sand & shale	870
sand & shells	1170
shale & shells	1310
sand & shells	1350
shale & shells	1380
anhydrite	1425
red bed & shale	1530
shale & shells	1880
lime & shale	2005
shale & lime shells	2110
shale & shells	2230
lime	2335
shale & lime	2460
lime	2665
lime brkn	2740
lime	2875
lime brkn	2905
lime & shale strks	3000
lime brkn	3050
lime	3190
lime & chert	3215
lime	3415
shale	3434
lime	3450

Total Depth.

Top Arbuckle Lime 3433

12-17-43 drld out cement  
plug & hole filled 1250'  
w/oil in 4 hrs  
12-21-43 Acidized thru 6"  
csg w/1000 Gals. from 3434-  
3449 in Arbuckle lime  
formation; Hole filled to  
1000' w/oil  
12-24-43 established Deptho.  
Pot. of 2911 BO, no wtr  
Total Depth 3449 in Arb. ls

Note: Above footages cal-  
culated from cement floor  
level, except formations.