

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


15-163-09403

CONTINENTAL OIL CO.
Dan Barry "B" No. 1.

SEC. 2 T. 9 R. 19 W
NE 1/4 SW
330'S 330'W Center

Total Depth. 3412' (3410' CFL)
Comm. 9-21-43 Comp. 10-7-43
Shot or Treated.
Contractor. Parker Drlg. Co.
Issued. 12-4-43

County. Rocks



CASING:
10 3/4" 239' Cem.
6" 3400' Cem.

Elevation.

Production. Max. Depth. Pot.
3000 B., Infinite Cap.
Figures Indicate Bottom of Formations.

cellar	0-30
shale-shells	245
shale	480
sand & shale strks	550
red bed	590
sand-shale	770
shale	975
shale-sand brkn	1100
shale-red bed	1350
red bed	1370
anhydrite	1420
shale-shells	1840
shale-lime	1975
shale-shells	2075
shale-lime	2410
lime	2475
lime-shale	2750
shale	2975
lime	3412
Total Depth.	

Top of Arbuckle Lime 3400
10-6-43 drld out cement plug
& hole filled 2800' w/oil
in 1 hr-deepened to 3410
10-9-43 estb. a max. allowed
depth. pot. of 3000 bbls oil.
Infinite capacity
Total depth 3410 in Arbuckle
Lime

Note: All above footages are
calculated from the cement
floor level, except formation
record.