

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


15-103-09393

Company - CONTINENTAL OIL CO.
Farm - Dan Barry "B" No. 3.

SEC. 2 T. 9 R. 19 W
NE NW SW
330'S 990' E W $\frac{1}{4}$ Cor.

Total Depth. 3443' (CFL 3441)
Comm. 1-31-44 Comp. 3-6-44
Shot or Treated.
Contractor. Parker Drlg. Co.
Issued. 6-24-44

County. _____
Rocks
KANSAS



CASING;
10 $\frac{3}{4}$ " 239' Cem.
6" 3426' Cem.

Elevation. _____

Production. Deptho. Pot. 3000 B.
No Wtr (Ind. Cap. 20,318 B)

Figures Indicate Bottom of Formations.

surface soil	65
sand	85
shale & shells	710
sand	775
sand & shale	1090
red bed & shells	1160
shale & lime shells	1390
anhydrite	1405
lime	1450
lime brkn	1505
lime & shale	1620
shale & shells	1745
lime & shale	1850
shale & shells	1955
lime & brkn lime	2053
limebrkn	2143
lime & shale	2308
lime	2370
lime & shale	2450
lime	2724
lime & shale	3010
lime brkn	3054
lime	3125
lime & shale	3140
lime	3438
sandy lime	3440
lime	3443
Total Depth.	(CFL 3441)

Top Arbuckle Lime 3425

3-4-44 drld out cement plug:

Deepened to 3443;

Total fillup w/oil 2800'

3-9-44 acidized thru 2 $\frac{1}{2}$ " tbg
w/1000 gals.

3-10-44 estab a deptho pot, 3,000 B oil,
no wtr., Ind. Cap 20,318 bbls. oil da.

Total depth 3441' in Arbuckle lime

Note: All above footages calculated
from cement floor level, except form-
ations.