

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


15-163-01597

Company - CONTINENTAL OIL CO.
Farm - J.E. Slansky No. 4.

SEC. 2 T. 9 R. 19 W
NE SW NW
990' N 990' E W $\frac{1}{4}$ Cor.

Total Depth. 3440' (CFL 3438)
Comm. 2-22-44 Comp. 3-15-44
Shot or Treated.
Contractor. Parker Drlg. Co.
Issued. 8-5-44

County. Rocks
KANSAS



CASING:
10 $\frac{3}{4}$ " 239' Cem.
6" 3432' Cem.

Elevation. _____

Production. Pot. 158 B. Phy.

Figures Indicate Bottom of Formations.

surface clay	15
shale & shells	50
shale & sand	200
shale & shells	700
sand & shale	840
sand & shells	1125
red bed & shale	1295
shale & shells	1390
lime	1440
shale & lime	1500
shale & shells	1640
shale	1785
shale & lime	2045
shale	2130
lime	2240
lime & shale	2315
lime	2325
shale & shells	2365
shale & lime	2465
lime	2700
lime & shale	2785
lime & shale	2845
lime	2890
lime brkn	2965
shale & lime	3050
lime	3440
Total Depth.	

Top of Arbuckle Lime 3431

3-13-44 Drilled out cement plug
and hole filled 200' w/oil in
2 hrs. Deepened to 3438' & hole
filled 2000' w/oil in 7 hrs.
3-17-44 Acidized w/1000 gals acid,
through 2 $\frac{1}{2}$ " tubing fm 3431-3438
3-18-44 Estb. 24-hr Phy. Pot. 158 BO

Total depth 3438 in Arbuckle Lime

Note: Footages calculated from
cement floor level, except
formations