

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

15-163-03027


Company. SKELLY OIL COMPANY
Farm. Frank Postecil No. 3

SEC. 4 T. 9 R. 19W
SE NE NW
990' fr VL & 330' fr EL NW $\frac{1}{4}$

Total Depth. 3428'
Comm. 9-15-48 Comp. 10-13-48
Shot or Treated. Acidized
Contractor. Claude Wentworth Drlg. Co., Inc.
Issued. 2-12-49

County. Rooks

KANSAS



Elevation. 1982.2nd

Production. Pot. 3000 bbls.

CASING:
13-3/8" 195' Cem. w/175 Sx.
8-5/8" 1416' Cem. W/600 Sx.
5-1/2" 3424' SLM Cem. W/200 Sx.

Figures Indicate Bottom of Formations.

surface soil & clay	45
sand	75
sand & shale	195
shale & shells	460
sand & shale	975
sand	1085
red bed & shells	1410
shale & shells	1425
anhydrite	1462
shale & lime shells	1840
salt	1950
shale & lime	2140
shale	2250
lime & shale	2365
shale	2455
lime	2645
shale	2715
shale & lime	2815
shale & shells	2985
shale	3075
shale & lime	3175
lime	3425
RTD 3426 SLM	
gy & brwn xlyn dolo.	3428
Total Depth	

Tops:
Heebner Shale 3146
Lansing Lime 3187
Arbuckle Lime 3423

3262-72 fair por. & stain
3423-3426 slight por. & stain
3426-3428 porous & saturated

Acid. 10-13-48 W/300 gals. 3424-3428
" 10-15-48 W/600 gals. 3424-3428
by Dowell Inc.

Producing formation* Arbuckle Lime
3423' to 3428'

Prod. before acid 1/2 BPH
Prod after acid POB 12 hrs. W/Echometer
for ind. prod. 9837 Bbls. Estab. 24 hr.
SCC Pot. of 3000 Bbls.