

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- WENTWORTH & SONS & PHILLIPS
Farm- Ziegler No. 2

15-163-71420
SEC. 8 T. 9 R. 19W
NE SE SE

Total Depth. 3559

Comm. 9-2-49

Comp. 10-11-49


Shot or Treated.

Contractor.

Issued. 9-15-51

County Rocks

KANSAS



Elevation. 2064

Production. 84

CASING:

8 5/8" 150'

5 1/8" 3537'

Drillers log not available.

Figures Indicate Bottom of Formations.

3193-3198 spotted dark stain

3246-3256 Staining

3274-3279 show dark oil, no odor

3293-3304 Staining, no odor

3268-3313 D.S.T. open 1 hr. 13 mins.

fill oil & gas cut mud

3336-3340 Staining faint odor

3345-3350 show free oil, good odor

3335-3351 D.S.T. 1 hr. 13 mins. 1850

fill - 240' heavy oil & gas cut

watery mud. 840' oil (50%) and gas

cut muddy wtr. 780' salt wtr. w/trace

of oil.

3534 Tan to brown, mostly dense dolo.

show of dead oil, no odor, no rainbow.

Tops:

Cimarron anhyd. 1470

Topoka lime 3018

Hoebner blk shale 3224

Lansing-K.C. 3265

Marmaton shale 3494

Sooy congl.- 3508

Arb. dolo. 3534

Shows of oil, gas & wtr.: