

503 East Main
Wichita, Kansas

JUL 5 1969

GABRIEL-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

9-95-19W

15-163-20194

MC CLELLAN #3

100' N of NW SW SW Section 9-95-19W

Rooks County, Kansas

Commenced: March 22, 1969

Completed: March 29, 1969

9-9-19W
NW SW SW

oil

OPERATOR - O. A. Sutton

DEPTH		FORMATION	REMARKS
From	To		
0	50	Surface clay	
50	203	Shale	Ran 10 joints of 8-5/8" casing, set @ 203' w/175 sacks of HA5.
203	587	Shale	
587	630	Sand	
630	856	Shale and sand streaks	
856	862	Hard sand	
862	895	Shale	
895	975	Shale and shells	
975	1215	Sand	
1215	1475	Shale	
1475	1486	Shale and red bed	
1486	1524	Anhydrite	
1524	1725	Shale and shells	
1725	2010	Shale	
2010	3270	Shale and lime	
3270	3557	Lime	
3557	TD		Ran 84 joints of 5-1/2" casing, set @ 3554' w/150 sacks salt saturated poz-mix.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled 100' N of NW SW SW Section 9-95-19W, Rooks County, Kansas, to the best of my knowledge and belief.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 2nd day of April, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

Richard O. [Signature]