

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-163-02297

Company- CONTINENTAL OIL CO.
 Farm- Dan Berry "C" No. 5

SEC. 10 T. 9 R. 19W
 NW NW NE

Total Depth. 3525'

Comm. 9-5-62

Comp. 9-12-62


Shot or Treated.

Contractor. Murfin Drlg.

Issued. 1-19-63

County Rooks

KANSAS



CASING:

10 3/4" 207' cem w/200 sx.
 7" 3551' cem w/275 sx.

Elevation. 2071' DF

Production. 50 BOPD, 50 BW

Figures Indicate Bottom of Formations.

post rock	40
clay	120
blue shale	210
shale	960
sand	1200
red bed	1410
shale & shell	1960
shale - lime	2150
lime & shale	2465
shale - lime	2625
lime	2700
lime & shale	3150
lime	3180
lime & shale	3310
lime	3525 RTD
Total Depth	

TOPS: SCOUT

Topeka	2989
Heebner	3193
Toronto	3215
Lansing	3234
Arbuckle	3479

DST #1 3140-3180', op 1 hr, Rec. 580'
 gassy oil, 50' muddy oil & 60' oil cut
 salt water. IBHP1087#, FBHP 1055#.