


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SOHIO PETROLEUM COMPANY
Farm- Rostocil "C" No. 1

15-163-01615
SEC. 10 T. 9 R. 19W
NW NW NW

Total Depth. 3459
Comm. 5-15-50 Comp. 5-30-50
Shot or Treated.
Contractor.
Issued. 1-3-53

County Rooks
KANSAS



CASING:

8 5/8" 309' cem. w/175 sx
5 1/2" 3457' cem. w/150 sx

Elevation. 2030 DF
2032 (21)
Production. 87 BO & 13% wtr.

Figure 1. Note Bottom of Formations.

soil, shale & shells	120
shale & shells	575
sand	605
shale & shells	915
sand	1165
red bed & shale	1435
anhydrite top	1455
anhydrite	1485
shale & shells	1675
shale & lime	1980
lime	2050
lime & shale	3075
lime	3459 RTD
Total Depth	

Tops:
Heebner 3165
Lansing 3211
Arbuckle 3448

DST: 3344-90' tool open 1 hr.
rec. 195' of heavily oil and
gas cut mud BHP 0
DST: 3404-20' tool open 30 mins.
good to strong blow, rec. 278' of
muddy salt wtr. BHP 950#.