

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY

508 E. Hurlock,

Wichita, Kansas

15-103-0107


Company - S HIO PETRO. CO.
 Farm - Rostocil "C" No. 3

SEC. 10 T. 9 R. 19N
 CS $\frac{1}{2}$ NE NW

Total Depth. 3445.48 R.B.M.
 Comm. 7-23-50 Comp. 8-4-50
 Shot or Treated.
 Contractor. Strain Drlg.
 Issued. 10-7-50

County. Books

KANSAS



CASING:

8 5/8" 330' com. w/175 sx.
 5 1/2" 3444 1/2' com. w/150 sx.

Elevation. 2039 DF

3041 Ind.
 Production. Ind. cap. 94,072
 BOPD

Figures Indicate Bottom of Formations.

cellar	5
post rock & clay	150
shale blue	200
shale blue & lime	
shells	330
shale & shells	620
sand	660
shale & shells	820
iron & pyrite	824 ✓
shale & shells	925
sand	1170
shale & shells	1448
anhyd.	1470
shale & shells	1800
lime & shale	2150
lime	2180
lime & shale	3100
lime	3444
lime	3445.48 R.B.M.
Total Depth	

Tops:
 Anhyd. 1448-1470
 Topeka 2953
 Hoebner 3155-3158
 Lansing 3195
 Arbuckle 3441

D.S.T. 3200-3225' tool open 30 min.
 Rec. good steady blow, 300' heavily oil
 cut mud. BHP 10 min. 1150#. flowing press.
 -O.
 Run Schlumberger and Micro. Log at total depth.