

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock Wichita, Kansas


Company - SOHIO PETROLEUM COMPANY
Farm - Rostocil "C" No. 4

15-163-01618
SEC. 10 T. 9 R. 19W
SE NW NW

Total Depth. 3443
Comm. 8-8-50 Comp. 8-19-50
Shot or Treated.
Contractor. Strain Drlg. Co.
Issued. 10-21-50

County. Rooks

KANSAS



CASING:
8 5/8" 310' com. w/175 sx
5 1/2" 3440 1/2' com. w/150 sx

Elevation. 2023 DF

Production. 3000 bbls. oil

Figures Indicate Bottom of Formations.

All measurements from rotary bushings:

collar	5
post rock & clay	150
blue shalo	275
shale & shells	915
sand	1140
shalo & shells	1335
sand & shalo	1425
Anhydrite	1468
shalo & shells	1800
limo & shalo	3165
limo	3443
Total depth	

Tops:	
Anhydrite	1445
Topoka	2950
Hoebner	3154
Lansing	3193
Arbucklo	3439

Remarks:

D.S.T. by Johnson Testing Co.
3195' to 3225' tool open 1 hr.
Weak steady blow through out.
Recovered 120' heavily oil cut
mud. B.H.P. 10 min. 1070#.
F.P.-0
3355 to 3380 tool open 1 hr.
Rec. 35' heavily oil cut mud.
B.H.P. 15 min. 320#. F.P.-0