

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

15-163-90939

CONTINENTAL OIL CO.
Dan Barry No. 2.

SEC. 11 T. 9 R. 19 W
NE NW NE
330'S 990'E N $\frac{1}{2}$ Cor.

Total Depth. 3473' (3468 CFL)
Comm. 4-29-43 Comp. 6-22-43
Shot or Treated.
Contractor. Parker Drlg. Co.
Issued. 8-14-43

County. Rooks



CASING:

10 $\frac{3}{4}$ " 247' Cem.
6" 3466' Cem.

Elevation.

Production. Phy. Pot. 700 B.
No wtr

Figures Indicate Bottom of Formations.

surface clay	0-50
sand	80
shale blue	250
shale & shells	500
sand & shale	1120
shale & lime shells	1215
shale & lime	1400
anhydrite	1465
shale & shells	1955
lime shells	2040
shale & lime	2255
shale & lime shells	2312
shale & lime	2444
lime & shale strks	2520
shale & lime	2635
lime & shale strks	2735
lime & shale	2848
lime & shale strks	2975
shale & lime	3157
lime	3277
lime & shale	3330
lime	3473
Total Depth.	

Tops: Anhydrite 1400
Arbuckle Lime 3465

6-22-43 drld out cement &
hole filled 800' w/oil in
6 hrs
6-23-43 swbd 12 BO in 4 hrs-
acidized w/500 gals acid-
hole filled 1000' in 8 hrs
6-25-43 acidized w/1000
gals. acid & started potential
6-26-43 established a 24-hr
physical potential of 700
bbls oil, no wtr

Total Depth. 3468' in Arbuckle
lime

Note: All footages calculated
from cement floor level
except formation record