


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - AYLWARD DRILLING CO.
Farm - Thyaft No. 1

15-163-00052
SEC. 11 T. 9 R. 19W
NE NW SW

Total Depth. 3565
Comm. 6-4-46 Comp. 6-22-46
Shot or Treated.
Contractor. Aylward Drilling Co.
Issued. 8-10-46

County. Rocks KANSAS



CASING:
8 5/8" - 290'
5 1/2" - 3565'

Elevation. 2049 ft

Production. Dry

Figures Indicate Bottom of Formations.

Surface Clay & Shale	60
Sand	85
Shale	450
Sand	510
Shale	645
Shale & Shells	780
Sand & Shale	810
Lime & Shale	920
Sand & Shale	1152
Lime & Shale	1270
Shale	1315
Sand	1340
Shale	1415
Sand	1455
Anhydrite & lime	1485
Red Bed	1570
Shale	1750
Salt	1845
lime & Shale	2010
Shale	2100
Shale & Shells	2260
Lime & Shale	2375
Shale	2515
Shale & Shells	2625
Lime & Shale	2730
Lime	2755
Shale	2840
Lime, broken	2985
Lime & Shale	3210
Lime	3440
Lime & Shale	3565
Total Depth	
Tops:	
Lansing	3189
Shaly Congl.	3462
Arbuckle	3532

Oil shows in Lansing:

3195-98 - very light oil show
3240-42- " " " "
3309-11 " " " "
3326-29 Some fair staining
3382-89 soft no odor or sat.
3422-25 Whole zone should be
tested-3422-41
3428-34

3433-41 Fair spotted Sat.

Lane Wells Shots from 3416 to 3440 Little water show oil Acidized 2/500 Gal.
Acid. After acid, made 100 gal water & 3 gal oil over night.

Lane Wells 10 Shots from 3377 to 3385 1/2 B.W.P.H.

Lane Wells 8 Shots from 3320 3327 Dry

Lane Wells 7 Shots from 3303 3309 Little rotary mud

Lane Wells 7 Shots from 3234 3240 Dry

Lane Wells 8 Shots from 3189 3196 Rotary mud 3190 to 3193 rest dry 2 B.W.P.H.

Hole filled 440' water - 2 Gal. in 14 Hr.