

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


15-163-03036

Company - SKELLY OIL CO.
Farm - Cora A. Hilgers No. 3

SEC. 12 T. 9 R. 19 W
SE NE SE
330' fEL & 1650' fSL SE $\frac{1}{4}$

Total Depth. 3489' PB 3485'
Comm. 3-29-47 Comp. 4-20-47
Shot or Treated. Acidized w/500 gals.
Contractor. Claude Wentworth Co.
Issued. 8-9-47

County. Rocks
KANSAS



Elevation. 2073 Sch. PB

Production. Depth. Pot. 3000 BO.

CASING:

13" 200' Cem. w/150 sx.
8 5/8" 1432' Cem. w/375 sx.
5 1/2" 3481' SLM Cem. w/200 sx.

Figures Indicate Bottom of Formations.

		Tops:	
surface soil, shale & shells	0-200	Anhydrite	1427
shale & shells	250	Lansing Limo	3242
shale	525	Arbuckle Limo	3480 SLM
sand	690		
red bed	840	Acidized 4-22-27 w/500 gals. acid.	
pyritic sand & shale	1090	3483-86'.	
sand & shale	1130		
red bed	1427		
anhydrite	1470		
red bed	1560		
shale & shells	1860		
shale & lime	2100		
shale	2150		
limo	2310		
lime & shale	2440		
shale red	2490		
limo & shale	2500		
lime brkn	2615		
lime	2660		
lime & shale	3055		
shale	3090		
lime & shale	3145		
limo	3325		
lime brwn & gy oolitic por. & sat.	3330		
lime	3410		
lime gy & brwn oolitic por. & sat.	3415		
limo	3435		
lime gy oolitic, por., sli, sat.	3439		
lime	3465		
lime gy oolitic, por. & sli. sat.	3470		
lime & shale	3485		
dolomito gy & brwn finely xlyn, sli. por. & stain	3488		
dolomito brwn coarsely xlyn, por. & sat., sft.	3490		
SLM Corr.			
3490 SLM R.T.=	3485		
SLM DF			
show of free oil, 200' OIH in 2 hrs.			
dolomito gy & brwn coarsely xlyn fair por. & sat.	3489		
500' OIH in 3 hrs.,			
1000' OIH in 6 hrs.,			
2300' OIH in 9 hrs.,			
2542' OIH in 12 hrs.			
& 2573' OIH in 14 hrs.			
BHP 1040#.			
Total Depth	3489		
PB 3485'			