


WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company - HARRY GORE  
Farm - Ruder No. 6

SEC. 14 T. 9 R. 19W  
SW NE NE

Total Depth. 3476  
Comm. 3-23-50 Comp. 4-14-50  
Shot or Treated. 500 acid  
Contractor. Veeder Supply and Dev. Co.  
Issued. 5-13-50

County. Rocks  
KANSAS



Elevation. 2063 (m)  
2067 Ind

CASING:  
8 5/8" 1436' cem w/650 sx.  
5 1/2" 3472' cem w/125 sx.

Production. 259 bbls oil / 52 %  
water

Figures Indicate Bottom of Formations.

surface soil, shale	40
sand shale	150
shale	400
shale shells	871
iron, sand, shale	895
iron, shale, shells	1009
iron shale	1105
sand iron	1170
red bed iron	1185
red bed	1200
red bed iron	1425
anhyd.	1468
red bed	1515
sand	1690
sand shale	1770
shale sand lime	1925
sand shale	2005
lime sdy shale	2045
lime shale sand	2170
lime sdy	2235
lime sdy, shale	2340
lime	2395
lime shale	2500
lime brkn	2580
lime	2645
lime shale	2750
shale lime shells	2815
lime shale	2995
lime	3145
lime shale	3150
lime	3235
lime cherty	3270
lime	3420
lime shale	3475
dolomite	3476
Total depth	

Tops:  
Topeka 2986  
Heebner 3192  
Dodge 3211  
Lansing 3229  
Arbuckle 3471

DST 3397-3412, open 30"  
rec. 120' oil and 3" mud.