

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


15-163-02747

Company- WESTGATE-GREENLAND & MID-PLAINS OIL CORP.  
 Farm- Casey No. 2

SEC. 15 T. 9 R. 19W  
 SE SE NW

Total Depth. 3530  
 Comm. 5-15-52 Comp. 6-8-52  
 Shot or Treated.  
 Contractor. B & R Drilling Co.  
 Issued. 7-5-52

County Rooks  
 KANSAS



CASING:  
 10 3/4" 209' cem w/165 sx  
 7" 3506 RB cem w/100 sx

Elevation. 2078 D.F.

Production. dry

Figures Indicate Bottom of Formations.

clay, sand	40
sand, gravel, shale	105
shale, shells	215
shale	680
sand, shale, shells	730
shale, shells	955
sand	1115
sand, iron	1190
shale, redbed, salt	1260
red bed, shale	1445
redbed	1456
anhydrite	1502
shale, redbed, shells	1600
lime, shale	2050
lime	2087
lime, shale	3110
lime	3150
lime, shale	3244
lime	3484
lime, shale	3506
lime arbuckle	3509

T.D. RB - Rotary  
 Cardwell 3506-3530  
 lime 3530  
 Total Depth

Tops:  
 Anhydrite 1456  
 Heebner 3223  
 Dodge 3243  
 Lansing 3264  
 Arbuckle 3504

Drill Stem Tests:  
 3229-51, op 1/2 hr, rec. 15' mud, no BHP  
 3281-3309, 1 hr, 260' SW, 1150# BHP

Ran Schlumberger  
 Drilled plug & made 4' new  
 hole, little free oil, perf.  
 w/jet gun, 500 GA, bailed  
 23 gal. water 1 gal dodd oil  
 ph. Let set over night, bailed  
 42 gals. fluid, 32 of it acid  
 water & 5 oil., 1500 GA, no  
 results. deepended to 3530,  
 swabbed 3 1/2 bbl fluid (1/3 bbls  
 of it was oil) 12 shots 3505 1/2-  
 07, no results. PB 3484-88;  
 perf. 12 shots 3436-46, no results.  
 Perf. 11 shot 3398- 3406, swab 2  
 gal oil, 40 tal water in 1 hr.  
 Dry & abandoned.