

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-163-00887

Company. STERLING DRILLING CO., ET AL
 Farm- Bartos 'A' (d.) No. 1

SEC. 22 T. 9 R. 19W
 SE SE NE

Total Depth. 3589'

Comm. 1-5-55

Comp. 1-23-55


Shot or Treated.

Contractor. Group Exploration Co. & Red Crow Drlg. Co.

Issued. 4-23-55

County Rooks

KANSAS



CASING:

8 5/8" 200' w/125 sx cem.

5 1/2" 3580' w/100 sx cem.

Elevation. 2161

Production. 35 BOPD

Figures indicate Bottom of Formations.

soil-sand	70
shale-shells	200
shale	750
sand-shale	1250
shale-limestone	1525
limestone	1560
shale	2000
limestone-shale	2700
limestone	2775
limestone-shale	3125
limestone	3303
Heebner sand	3343
limestone	3568
limestone-shale	3580
Arbuckle	3586
Total Depth	

TOPS: Scout

Heebner	3303
Lansing	3345
Arbuckle	3577

CABLE TOOLS: M.I.C.T. Swabbed mud,
 drilled cement & shoe. Cleqned out
 to 3586' T.D. and drilled new hole to
 3589'. Bail tested @ rate of 1 1/2 bbls.
 oil per hr. Acidized w/1000 gals.
 acid & swabbed back load oil. Test-
 ed @ rate of 20 bbls. oil per hr.
 Ran tubing & rods. P.O.P.