

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company -DERBY OIL COMPANY
Farm -Jelinok

No. 2

SEC. 23 T. 9 R. 19W
SE NE SE

Total Depth. 3558'

Comm. 4-27-48

Comp. 5-18-48


Shot or Treated.

Contractor. G. W. Peel

Issued. 8-28-48

County. Rooks

KANSAS



Elevation. 2137' 2nd

Production. 3000 Bbls.

CASING:

11" 256' Cem w/125 Sx. at surface

7 7/8" 3546' Cem. w/100 Sx at 2950

Figures Indicate Bottom of Formations.

shale & sand	257
shale	482
shells & shale	625
sand	715
shale	810
?	955
lime	1170
sand	1240
lime & shale	1425
shale	1436
lime & anhydrite	1458
lime & shale	1525
shale & shells	1675
broken lime	1870
shale	1902
shale & lime	2028
lime & shale	2308
lime	2784
shale & lime	2956
lime & shale	3074
lime	3512
shale & lime	3546
dolo	3558
total depth	

Tops:

Lansing	3303
B/Kansas City	3508
Arbuckle	3546

No Drill Stem Tests

Completion Record:

Drilled plug & D. D. to 3554.

Swabbed 8 1/2 BOPH off bottom.

Drilled deeper to 3558 T.D.

Swabbed 32 BOPH 4 hrs. 400'

off bottom. Fill up 2450'

1 hr. Treated with 1000

acid. Swabbed 51 BOPH 2

hrs. 1800 ft. off bottom.

No water.

Remarks

Gd. show oil 3473 to 3480.

Slight show oil 3338 to 48.

Fair porosity, fair odor
with free oil break 3547
to 49.