

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


15-1103-03052

Company - BAY PETROLEUM CORP.
Farm - Benoit No. 1

SEC. 26 T. 9 S. 19W
NE NE NE

Total Depth. 3579'
Comm. 12-11-48 Comp. 12-31-48
Shot or Treated.
Contractor. L-S-T drlg. Co., Inc.
Issued. 4-2-49

County. Rooks
KANSAS



8-5/8" CASING: 236' 5 1/2" 3577'

Elevation. 2169' Ind.

Production. D.D. 1656 BOPD, no wtr.

Figures Indicate Bottom of Formations.

clay, sand & shale	225
shale & shells	875
sand & shale	960
shale	1020
sand & shale	1330
shale, lime & shells	1384
red bed & shells	1440
anhydrite	1568
shale & shells	1775
shale & lime	2300
li e	2795
lime & shale	2830
lime	3351
lime cherty	3370
lime	3579
Total Depth	

Tops:	
Anhydrite	1530
Heebner	3297
Toronto	3316
Lensing	3337
Arbuckle	3576

Swab. 15 OPH, no wtr
Swab 40 BOPH/5 hrs,

Drawdown test: 1656 BOPD, no wtr.