

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

Company CITIES SERVICE OIL COMPANY
Farm Bartos No. 1

15-163-01694
SEC. 27 T. 9 R. 19W
SWc NE
330' N & 330' E of C

Total Depth 3629'

Comm. 12-17-47 Comp. 1-13-48


Shot or Treated. 500 gals. (1-18-48)

Contractor. R. W. Rine Drilling Co.

Issued 2-28-48

County. Rocks

KANSAS



CASING:

8 5/8" 304' cem. w/150 sx & 100# CC
5 1/2" 3623' cem. w/150 sx

2183 rh
Elevation. 2210 ind

Production. Echometer Pot:

3000 BO & no wtr, 24 hrs.

Figures Indicate Bottom of Formations.

sand, shale & shells	0-1195
shale & sand	1565
anhydrite	1595
shale & shells	2145
shale & lime	2335
lime	2460
lime & shale	3300
lime	3435
lime & chert	3580
lime	3621
3621 Rot. TD = 3625 SLM	
lime	3629
Total Depth	

TOPS: (CORR.)

Lansing	3375'
Arbuckle	3622'

Penetration 7'

Fillup:

400'	Oil in 40 mins.
500'	" " 50 mins.
860'	" " 1 1/2 hours
1400'	" " 3 1/2 "
2100'	" " 5 1/2 "
2335'	" " 7 1/2 "
2450'	" " 9 1/2 "

Echometer Potential: 3,000 O
no water, 24 hrs. (1-20-48)
Inc. Cap. 10,270 bbls.