

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Bartos No. 2

15-103-01695
SEC. 27 T. 9 R. 19W
S4 NW NE
990' S & 330' E of N/4 Corner

Total Depth. 3633'
Comm. 9-24-48 Comp. 10-6-48
Shot or Treated. Acid. w/500 gals. 10-20-48
Contractor. Holm Drlg. Co.
Issued. 2-12-49

County. Rooks
KANSAS



CASING:

8-5/8" 307' Cem. w/200 Sx.
5-1/2" 3630' Cem. w/150 Sx.

Elevation. 2208 2nd

2208 set
Production. Draw-down pot. 3000
oil, 15 wtr, 24 hrs. Ind.
cap. 4014 BPD.

Figures Indicate Bottom of Formations.

surface clay & sand	80
shale & shells	307
shale	765
red shale	790
shale	870
sand & shale	1080
sand	1200
shale	1260
shale & shells	1320
red bed & shells	1462
anhydrite	1515
shale & shells	1775
shale	1925
shale & lime	2100
shale & lime shells	2175
lime	2230
shale & lime	2320
shale	2335
shale & lime	2670
lime & shale	3200
lime	3225
lime & shale	3370
lime	3515
pyrite & chert	3518
lime	3633
3633 RTD = 3633 SLM	
Total Depth	

Tops:
Lansing 3375
Arbuckle 3629
Penetration 4

Fillup:

300' oil in 40 mins.
700' oil in 1 1/4 hrs.
1050' oil in 3 hrs.
1350' oil in 5 hrs.