

gnd

Purchaser.....none.....

 ESTELLE L. SCHROLLEN
NOTARY PUBLIC
STATE OF KANSAS
APPT. EXPIRES 4-10-92

01042

WB 1-A-12

SIDE TWO

Operator Name QB VI Lease Name Webster Well # 1

Sec 34 Twp 9 Rge 19 East West County Rooks

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken [X] Yes [] No
Samples Sent to Geological Survey [] Yes [X] No
Cores Taken [] Yes [X] No
3416 - 3431'
DST #1: times 15-35-45-45",
IHM 1708#, IFP 74 - 74#, ISIP 180#,
FFP 127 - 148#, FSIP 190#, FHM 1645#,
temp. 104, MW 9.1, VIS. 50,
Recovered 25' gassy mud and 240' muddy water
chl. 55,000 ppm.

Formation Description
[X] Log [] Sample


Name	Top	Bottom
Anhydrite	1568	1614
Topeka	3146	3352
Heebner	3352	3373
L-KC	3392	3610
RTD		3660
Arbuckle not reached		

CASING RECORD [] New [] Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (in O.D.)	Weight Lbs/Ft.	Setting Depth	Type of Cement	#Sacks Used	Type and Percent Additives
Surface	12 1/4	8 5/8		250'	60/40	160	2%gel, 3%cc
PERFORATION RECORD				Acid, Fracture, Shot, Cement Squeeze Record			
Shots Per Foot	Specify Footage of Each Interval Perforated			(Amount and Kind of Material Used)			Depth
TUBING RECORD				Liner Run [] Yes [] No			
Date of First Production		Producing Method					
D&A		[] Flowing [] Pumping [] Gas Lift [] Other (explain).....					
Estimated Production Per 24 Hours	Oil	Gas	Water	Gas-Oil Ratio	Gravity		
	Bbls	MCF	Bbls	CFPB			

METHOD OF COMPLETION

Production Interval

Disposition of gas: [] Vented [] Open Hole [] Perforation
[] Sold [] Other (Specify)
[] Used on Lease
[] Dually Completed
[] Commingled



34-9-19W. *Ind*

WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: QB VI, P. O. Box 38, Paradise, KS 67658

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
Wichita, Ks. 67202

Lease Name Webster Well No. 1

Sec. 34 T. 9 S R. 19 W Spot SW NW SE

County Rooks State Kansas Elevation

Casing Record:

Surface: 8 5/8" @ 250' with 160 sx. 2% Gel 3% CC

Production: @ with sx.

Type Well: D & A Total Depth 3660'

Drilling Commenced 10-1-88 Drilling Completed 10-5-88

Formation	From	To	Tops
Cellar	0	7	
Shale, Lime	7	3660	

KANSAS GEOLOGICAL SURVEY
WICHITA BRANCH

OCT 18 1988