

434-4638

6 623-1524

BARRY D #4

spud: 10/31/49
compl: 11/11/49

TDC Surface
(Circ.)

ELEVATIONS:
GL 2029'
RKB 2030'

10 3/4" 32 lb/ft H-40
@ 224'
w/ 175 sx cmt

Csg Leak @ 1246'
Sqzd w/ 200 sx 1/58

TDC Unknown

LKC Perfs:

- 3207'-13' (A) 4/68 Sqzd 10/75
- 3247'-56' (B) 4/68 Sqzd 10/75
- 3262'-65' (D) 4/68 Sqzd 10/75
- 3282'-86' (F) 4/68 Sqzd 10/75
- 3340'-48' (H) 11/61 Sqzd 10/75
- 3360'-70' (I) 11/61 Sqzd 10/75
- 3379'-85' (J) 11/61 Sqzd 10/75
- 3400'-06' (K) 11/61 Sqzd 10/75

Arbuckle Perfs:

3454'-54' 11/61

Arbuckle D.H.:

3454'-61'

7' 20 lb/ft J-55
@ 3454'
w/ 200 sx cmt

TD 3461'

	OPERATOR	PHILLIPS PETROLEUM COMPANY	WELL NO.
	WELL NAME	Barry D	
	FIELD	Barry	STATE
	COUNTY	Rooks	DATE
	LOCATION	SW NE NE Sec. 11-19S-R19W	07/27/94